

APR 27 1995

CRAWFORD COUNTY PEER GROUP APPROVAL DATE Dec 29, 1994

LIBER 3 PAGE 165 COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF CRAWFORD

For corners in

Table with columns: Crawford (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

FILED FOR RECORD THIS 30th DAY OF Dec, 1994 AT 4:20 am/pm IN LIBER 3 PAGE 165.

Register of Deeds Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Marvin E. Myers, in a field survey on December 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-A.P. Brewer 1852 Mon-Set Post WIT: 9" S.Pine N80°W 14 lks. 8" S.Pine n35°E 8 lks. R.Ostling June 1946 Mon-Axel Shaft WIT: C County Road East 22.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found 3/4" x 6" iron pipe over 1" axle shaft in mon. box 1' South of centerline County Road 200 and 17.8' West of centerline South Grayling Road WIT: Fd. nail NW side 13" J.Pine (dead) S51°W 84.38' Fd. nail SW side U.Pole S49 1/2°E 62.29' Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set std. Crawford County Mon. stamped "T25N R3W E-13 31600" in mon. box over 1" axle shaft WIT: Set wit. tag & nail S. side 21" W.Pine N55°W 91.01' Set wit. tag & nail SW side U.Pole N24 1/2°W 84.10' Fd. nail SW side U.Pole S49 1/2°E 62.29' Set wit. tag & nail NW side 13" J.Pine S57°W 86.04' Fd. P.K. nail S89°E 17.33'



Signed by Marvin E. Myers

Date Dec 29, 1994

Surveyor's Michigan License No. 31600