

MAR 22 1999

LIBER 3 PAGE 322

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

Located in: Corner Code #

I. Public Land Survey	T25N R 3W	G-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 9:59 A.M.

SANDRA MOORE
REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey August, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

A.P. BREWER 1852, GLO SET POST Y. PINE 9° N8°W 17 LKS S. PINE 10° S71°E 45 LKS	F. ARLETH, RLS, 1979, L143, P15 MON - FD 1" PIPE NO WIT
G.D. HENNING, R.S 1977 LCRC L2, P161 PIPE MON FD 1" PIPE SET BY E.L. HOUGHTON 1905 8" B. OAK S22°W 119.0' 14" R. PINE N13°W 82.0' 8" MAPLE N29°E 68.2'	N. PARKER, RLS, 1983, L216, P136 MON - 1" PIPE 8" MAPLE N40°E 68.3' 14" R. PINE N7°W 82.0' 8" B. OAK S22°W 119.0'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 24" PIPE OVER REMAINS OF WOODEN POST
UPROOTED STUMP OF NORWAY PINE (NW)

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD CRAWFORD COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 9" OAK N72°E 77.75'
NAIL & TAG IN BRACE POST S33°E 57.31'
NAIL & TAG IN P. POLE S33°W 55.08'
CARSONITE POST N40°W 33.15'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Aug 21 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License No. 17614

Date Aug 28 1998