

MAR 22 1999

LIBER 3 PAGE 323

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

SECTION

For corners in
Crawford County

Located in: Corner Code #

1. Public Land Survey	T25N R 3W	II-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 9:59 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey August, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

A.P. BREWER 1852, GLO SET POST S. PINE 9° N47°W 119 LKS S. PINE 9° S17°E 150 LKS	G.D. HENNING, RLS, 1977 LCRC L2, P161 MON-SET 1/2" IRON BAR HALFWAY & ON LINE 8" J. PINE S29°E 47.6' 6" W. PINE S37°W 44.0' 30" OAK N45°30'W 42.95'
K.J. OSTLING, RLS 1954 DNR TOWNSHIP MAP INDICATES CORNER NOT FD . OR SET	N. PARKER, RLS, 1983 MON - 1/2" BAR WIT SAME AS ABOVE

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" STEEL BAR MIDWAY AND ON LINE
FOUND W. PINE WIT SE - BUT DEAD AND PUSHED OVER

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD CRAWFORD COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 11" W PINE S45°W 47.70'
NAIL & TAG IN 5" W. PINE N60° W 54.73'
NAIL & TAG IN 8" N. PINE S48°E 42.92'
NAIL & TAG IN 12" B. OAK N27°W 57.34'
CARSONITE POST SOUTH 25.85'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Aug 21, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date 8/24/98