

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Crawford County

**LIBER 4 PAGE 39**

Located in: Corner Code #

1. Public Land Survey

T25N	R3W	H-13
T	R	
T	R	
T	R	

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
 20th DAY OF Sept 19 1999 AT  
 9:00 am, IN LIBER 4  
 PAGE 39.  
 Sandra Moore.  
 Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey July 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838 SET QR SEC. POST TAMARACK 10° N43°W 61 LKS TAMARACK 10° N62°E 24 LKS	HAROLD NEFF, SURVEY CHIEF (MDOT) 1966 ½" IRON BOLT 6' J PINE 57.89° N34°E 10' J. PINE 57.03° S53°W 12' J. PINE 59.71° S44°E
GEORGE D. HENNING, CO SURVEY 1943 1/4 COR MIDWAY ON LINE 5.0' NORTH OF CENTERLINE OF PAVT B. SPRUCE 5° S46 1/2°E 59.5' N PINE 6° S43°W 57.0'	LCRC 1970'S LIBER 2, PAGE 506 SAME WITNESSES AS ABOVE
ROBERT T. OSTLING, RLS 1946 CHISLED CROSS IN PAVT 5' N OF CL B.T. SPRUCE 5° S46 1/2°E 59.5' B.T. N. PINE 6° S43°W 57.0'	LARRY L. CAVANAGH, PS 1996 NO MON MATERIAL MENTIONED SPIKE IN 5' J. PINE N29°W 92.13' FORM SEAM IN N SIDE OF CON BRIDGE PIER S35°W 12.01' FORM SEAM IN N SIDE OF CON BRIDGE PIER N88°E 61.92' SPIKE IN 12' TAMARACK S44°E 162.57'

FRANK J. ARLETH, PS 1997  
FD PAVT BOX

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND #40 SPIKE IN MEDIAN UNDER OVERPASS OF I-75 AND ALL OF L. CAVANAGH WITNESSES FROM 1996  
THIS POSITION IS MIDWAY AND ON LINE BETWEEN SECTION CORNERS 2644.42 G-1 TO H-1; 2644.42 H-1 TO I-1  
THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD MONUMENT UNDER OVER PASS. CENTER OF PAVEMENT BOX IN BRIDGE DECK 20'± ABOVE MONUMENT IS 0.65' NORTH OF CORNER  
WIT: NAIL & TAG IN 5' J. PINE N29°W 92.13'  
NAIL & TAG IN 12' TAMARACK S44°E 162.57'  
FORM SEAM IN NORTH SIDE OF CONCRETE BRIDGE PIER N88°E 61.92'  
FORM SEAM IN NORTH SIDE OF CONCRETE BRIDGE PIER S35°W 12.01'  
CARSONITE POST S16°E 8.4'

CRAWFORD COUNTY  
PEER GROUP APPROVAL

DATE Sept 10, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date Sept. 14, 1999

