

MAR 22 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

SECTION

For corners in  
Crawford County

Located in: Corner Code #

1. Public Land Survey	T25N R3W	I-7
	T_____R_____	_____
	T_____R_____	_____
	T_____R_____	_____

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

29 SEP 98 9:59 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey August, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

A.P. BREWER 1852, GLO SET POST Y. PINE 12" S52 3/4°E 10.06 LKS S. PINE 7" S69 1/2°W 59.5 LKS	G.D. HENNING, FLS, 1977 LCRC L2, P161 MON-DNR MON - 1" PIPE 8" J. PINE N65°E 67.0' 4" J. PINE S5°W 27.95' 8" J. PINE N13°W 32.05'
D.C. DELAMATER RLS 1954 LCRC L5, P15 MON - 1" PIPE (FD ONE ORIG BT STILL IN PLACE, FAIR CONDITION) 9" J. PINE N38°W 65 LKS 9" J. PINE N67°E 101 LKS	

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 3/8" PIPE  
4" J. PINE (NOW 7") S5°W

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD CRAWFORD COUNTY MONUMENT STAMPED 17614  
WIT: NAIL & TAG IN 7" J. PINE S5°W 28.20'  
NAIL & TAG IN 7" J. PINE S37°E 30.88'  
NAIL & TAG IN 3" OAK N45°W 38.55'  
NAIL & TAG IN 2" OAK N25°E 30.78'  
CARSONITE POST NORTH 24.65'

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Aug 21, 1998

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date Aug 28, 1998