

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County **LIBER**

Located in: **4** PAGE **40**
Corner Code #

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
29th DAY OF Sept, 1999 AT
9:00 AM, IN LIBER 4
PAGE 40
Shandra Moore
Register of Deeds

I. Public Land Survey
T25N R3W I-13
T R
T R
T R

I, Larry L. Cavanagh, in a field survey July 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:
JOHN BRINK, GLO 1838
SET POST COR SECS 34 & 35
BIRCH 10° N22°W 14 LKS
CEDAR 8° N75°E 13 LKS
ROBERT T. OSTLING, RLS 1946
SEC 2 SURVEY
PAVT BOX IN CENTERLINE OF PAVT
WILLIAM BURT, GLO, 1852
W. BIRCH 8° S49°E 12 LKS
CEDAR 5° S29°W 26 LKS
ROBERT T. OSTLING, RLS 1946
SEC 3 SURVEY
PAVT BOX 1.0' SOUTH OF HWY CENTERLINE
B.T. CEDAR S19 1/2°E 72.5'
B.T. CEDAR S48°W 69.01'
GEORGE D. HENNING, CO. SURVEYOR 1943
HIGHWAY MONUMENT BOX 1.0' N OF
CENTERLINE OF PAVT
PLACED 1 1/4" X 24' IRON PIPE ON
ROW LINE S5°30'W 100' FROM
PAVT CENTERLINE
FRANK J. ARLETH, PS 1997
SURVEY L463, P334
FD PAVT BOX 2.0' NORTH OF CENTERLINE OF RD

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PAVT BOX, NO MONUMENT, 2.0' SOUTH OF CENTERLINE
CHECKED DISTANCE TO H-1 2644.42'
MDOT REF HUBS TO SOUTH 66.36' RECORDED 66.43'
95.75' RECORDED 95.83'
119.51' RECORDED 119.53'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD MONUMENT IN PAVEMENT BOX 2± SOUTH OF CENTERLINE
WT: NAIL & TAG IN 11" CEDAR S9°W 65.27'
NAIL & TAG IN 6" CEDAR S20°E 71.26'
NAIL & TAG IN 4" BALSAM N45°E 77.38'
NAIL & TAG IN 6" SPRUCE N3°E 88.59'
CARSONITE POST SOUTH 41.5'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Sept 10, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date Sept 14, 1999
Surveyor's Michigan License NO. 17614