

**SURVEY &
REMONUMENTATION**

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

SECTION

For corners in
Crawford County

LIBER

3

PAGE 277

Located in:

Corner Code #

1. Public Land Survey

T26N R3W
T25N R3W
T R
T R

J-13
J-1

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
30 DAY OF Nov, 1997 AT
9:30 am, IN LIBER 3 of L
PAGE 277

Andrea Moore

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON P. BREWER
SET POST
PINE 12 N46W 45
PINE 4 N43E 21

JOHN I. NELSON 21273
LCRC L2 P247 1982
SET 5/8" REROD WITH CAP
SET NAIL W/RLS TAG 212L73 IN SE SIDE OF 10" OAK AZ 53° 87.82'
SET NAIL W/RLS TAG 21273 IN NORTH SIDE OF 14" OAK AZ 117° 100.71'
SET NAIL W/RLS TAG 21273 IN NW SIDE OF 16" OAK AZ 242° 96.39'
SET NAIL W/RLS TAG 21273 IN SOUTH SIDE OF P. POLE AZ 287° 130.13'

[Handwritten signature]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 5/8" X18" STEEL ROD OVER 1" PIPE (LEFT IN PLACE)
SET NAIL W/RLS TAG 212L73 IN SE SIDE OF 10" OAK AZ 53° 87.82'
SET NAIL W/RLS TAG 21273 IN NORTH SIDE OF 14" OAK AZ 117° 100.71'
SET NAIL W/RLS TAG 21273 IN SOUTH SIDE OF P. POLE AZ 287° 130.13'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CRAWFORD COUNTY MONUMENT STAMPED 17614 1997
NAIL & TAG IN 19" NORWAY S40°W 40.35'
NAIL & TAG IN 18" B. OAK S65°E 100.59'
NAIL & TAG IN 15" J. PINE N51°E 87.73'
NAIL & TAG IN P. POLE N75°W 130.01'
CARSONITE POST NORTH 33.75'

**CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE OCT 16, 1997**

Marvin E. Myers

**Marvin E. Myers, P.S.
County Surveyor**

A REESTABLISHMENT OF THE POSITION OF THE ORIGINAL GOVERNMENT CORNER.



Signed by *[Signature]*
Surveyor's Michigan License NO. 17614

Date *Oct. 22, 1997*