

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

LIBER

3 PAGE 278

STATE OF MICHIGAN
COUNTY OF CRAWFORD

Located in:

Corner Code #

1. Public Land Survey

T 26N R 3W
T 25N R 3W
R
R

K-13
K-T

FILED FOR RECORD THIS
30 DAY OF Nov, 1997 AT
9:30 am/pm, IN LIBER 3 OF LC
PAGE 278

Sandra Moore
Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON P. BREWER
SET POST
PINE 8 N59°W 36
PINE N68°E 16

KENNETH J. OSTLING
1954 PIPE BY PREVIOUS SURVEY
NO WITNESSES

KENNETH J. OSTLING 1979
FD 1 1/2 PIPE, RAISED W/3/4" PIPE
AT ROAD INTERSECTION
NO WITNESSES

KENNETH J. OSTLING 10068
LCRC L2 P217 1979
FD 1 1/2" PIPE RAISED W/3/4" PIPE
16" OAK (N.P.) S37°E 95.92'
12" OAK (N.P.) S43°W 91.28'
CEDAR POST SE 92'

NORMAN F. PARKER 16939
LCRC L2 P259 1983
1/2" BAR IN BLACKTOP OVER IRON
P.K. NAIL IN N SIDE P. POLE S51°W 42.75'
P.K. NAIL IN N SIDE P. POLE S69°E 106.45'
TW 12" OAK N556E 53.6'

JOHN I. NELSON 21273, LCRC L2 P245 1982
FD 3/4" IRON PIPE
SET NAIL W/RLS TAG 21273 IN S SIDE P. POLE AZ 72° 102.08'
FD NAIL W/RLS TAG 16939 IN NW SIDE 16" OAK AZ 141° 96.10'
SET NAIL W/RLS TAG 21273 IN W SIDE 12" OAK AZ 222° 91.74'
SET NAIL W/RLS TAG 21273 IN SW SIDE 8" MAPLE AZ 332° 77.40'



	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 3/4" X 12" PIPE OVER 1 1/2" PIPE COULD NOT REMOVE
NAIL W/RLS TAG 21273 IN S SIDE P. POLE AZ 72° 102.08'
NAIL W/RLS TAG 16939 IN NW SIDE 16" OAK AZ 141° 96.10'
NAIL W/RLS TAG 21273 IN W SIDE 12" OAK AZ 222° 91.74'
NAIL W/RLS TAG 21273 IN SW SIDE 8" MAPLE AZ 332° 77.40'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CRAWFORD COUNTY MONUMENT STAMPED 17614 1997
NAIL & TAG IN P. POLE N70°E 102.25'
NAIL & TAG IN 10" MAPLE N30°W 77.34'
NAIL & TAG IN 18" B. OAK S42°E 96.81'
NAIL & TAG IN 14" B. OAK S39°W 91.71'
CARSONITE POST N45°E 63.22'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE OCT 16, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date Oct. 22, 1997