

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

LIBER

4

PAGE

42

Located in:

Corner Code #

1. Public Land Survey

T25N R3W
T R
T R
T R

K-13

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
29th DAY OF Sept, 1999 AT
9:00 am, IN LIBER 4
PAGE 42
Sandra Moore

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey July 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK, GLO 1838
SET POST COR SECS 35 & 36
BEECH 10" N72°W 41 LKS
BEECH 9" N25°E 33 LKS

G. D. HENNING, RLS 1953
"CENTERLINE OF HIGHWAY & 1/4 LINE SOUTH"
NO MONUMENT MENTIONED

WILLIAM BURT, GLO, 1852
HEMLOCK 20" S31°E 25 LKS
BEECH 8" S76°W 14 LKS

FRANK J. ARLETH, 1990
SURVEY, L339, P381
FD PK NAIL OVER PAVT BOX
12" ELM N20°W 74.4'
1/2" BAR S5°51'20"W 105.0'

ROBERT T. OSTLING, RLS, 1946
SECTION SURVEY
BOLT IN PAVT 11.2' W OF PAVT
BOX FOR SEC COR
SPIKE IN ELM 24" N69°E 75.0'
SPIKE IN ELM 12" N29°W 74.4'

LARRY L. CAVANAGH, PS SURVEY 1997
SET PK NAIL FROM WIT AND SURVEYS OF RECORD
1/2" BAR S5°51'53"W 105.0'
P. POLE N17°W 94.04'
12" W. PINE N68°E 138.84'
6" J. PINE S36°E 63.27'
P. POLE S27°W 110.50'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

LARRY L. CAVANAGH, PS 1998
FD PK NAIL
WITNESS SAME AS ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

IN 1997 A PK NAIL WAS SET AT CORNER LOCATION BY MEASUREMENT FROM PREVIOUS SURVEYS OF RECORD
ALL 1997 WITNESSES WERE RECOVERED (PK NAIL NOT FOUND)
CORNER SET FROM 1997 WITNESSES

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD MONUMENT IN PAVEMENT BOX 4± NORTH OF CENTERLINE OF M-76, 2± EAST OF THE CENTERLINE OF NOLAN ROAD
WIT: NAIL & TAG IN P. POLE N17°W 94.04"
NAIL & TAG IN 12" W. PINE N68°E 138.84'
NAIL & TAG IN 6" J. PINE S36°E 63.27'
NAIL & TAG IN P. POLE S27°W 110.50'
1/2" BAR S5°52'W 105.0'
CARSONITE POST N35°W 53.35'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Sept 10, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date Sept. 14, 1999

