

**SURVEY &
REMONUMENTATION**

MAR 22 1999

SECTION

LIBER 3 PAGE 329
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------|-------|
| 1. Public Land Survey | T 25N R 3W | M-9 ✓ |
| | T 25N R 2W | A-9 — |
| | T — R — | — |
| | T — R — | — |
| 2. Property Controlling
in Section | S — T — R — | — |
| | S — T — R — | — |
| 3. Miscellaneous
Property in Sec. | S — T — R — | — |
| | S — T — R — | — |

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 10:00 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on July 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2	8		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		38	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O – 1839 John Brink, DS Mon. - Post 8" Pine S73°W 28 lks. 18" Pine N72°W 76 lks.	L.4 P.1-14 Indian Glens of the AuSable #6 Oct 1973 B. Feldhauser 10085 Mon – Concrete plat mon
---	--

GLO – Aug 1852
Mon - Post
12" Spruce Pine N42°E 52 lks
12" Spruce Pine S58°E 13 lks

L.3 P.25 Indian Glens of the AuSable #5
Aug 1971 C E Ostling 12026
Mon – Concrete plat mon

**CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE August 21, 1998**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete plat monument 35± South of old E-W Trail road. Accepted as the best available evidence of the position of the Original Corner. Replaced concrete monument with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon – Standard Crawford County Monument.
Wit: Set nail & tag N. side 4" Maple S57°E 17.27
Set nail & tag E. side 22" Oak S09°W 17.16
Set nail & tag N. side 12" Oak S74°W 24.69
Set nail & tag W. side 4" Oak N35°E 13.36
Set Carsonite Post North 1.0



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date Aug 24, 1998