

SURVEY & REMONUMENTATION

MAR 22 1999

LIBER 3 PAGE 332

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N R 3W
T 25N R 2W
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

M-12 ✓
A-12

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 10:01 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on July 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O – 1839 John Brink, DS Aug 1949 R.T. Ostling May 31 1953 G.F. Henning 2240
Mon. - Post Mon - 4" Sq. Post Mon – not given
18" Y. Pine S88°W 33 lks.
18" Y. Pine N74°W 18 lks. L160, P555 G.D. Henning 2240 Jun 1972
Mon – Concrete Mon.
L3, P10 Indian Glens of the AuSable
Jan 1970 C.E. Ostling 12026
Mon – Concrete Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Concrete Monument as called for in Liber 3 of Plats, Page 10, Indian Glens of the AuSable at fence line intersection North & East. Accepted as the best available evidence of the position of the Original Corner. Replaced Concrete Monument with Standard Crawford County Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon – Standard Crawford County monument.
Wit: Set Carsonite Post South 1.0
Set Nail & tag in S. side of RR tie Fence Post East 6.95
Set nail & tag in E. side 7" White Pine S14°W 5.30
Set nail & tag in NE side 6" Maple clump N77°W 16.83
Set nail & tag in SW side 6" Maple N21°W 22.80

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Aug 21, 1998

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by _____

Date Aug 24, 1998

Surveyor's Michigan License No. 31600