

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--                      | LOCATED IN--        | CORNER CODE NUMBER |
|---------------------------------------|---------------------|--------------------|
| 1. PUBLIC LAND SURVEY                 | T. 25 N. R. 3 W.    | K-1; K-2           |
| 2. PROPERTY CONTROLLING IN SECTION    | 1, T. 25 N. R. 3 W. | 16                 |
| 3. MISCELLANEOUS PROPERTY IN SECTION  | 1, T. 25 N. R. 3 W. | K-3/10             |
| 4. LOT NO. _____, RECORDED PLAT _____ |                     |                    |
| 5. PRIVATE CLAIMS _____               |                     |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 8, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on April 9, 1979, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories and/or subsequent restoration:

C. (continued)

K-3/10  
Set 5/8" Rod w/RLS Cap & ced. post  
4" J. Pine N65°W 43.41  
3" J. Pine S70°W 43.92  
3/4" Rod S82°E 35.0  
Cedar Post East 35

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1 Found corner in place from previous surveys at road intersection. Rewitnessed for proper recording.
- K-2 Found corner as previously established by G. D. Henning and found and used in DNR 1969 survey.
- 16 Set corner by standard survey procedure for the subdivision of sections.
- K-3/10 Set proper ty corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| K-1                             | K-2                           | 16                                |
|---------------------------------|-------------------------------|-----------------------------------|
| Fd. 1½" pipe raised w/3/4" pipe | Fd. ½" Rod raised w/3/4" Pipe | Set 5/8" Rod w/RLS Cap & ced.post |
| 16" Oak (N.P.) S37°E 95.92      | 12" R. Pine N34°W 84.95       | 6" J. Pine N89°E 12.8             |
| 12" Oak (N.P.) S43°W 91.28      | 12" R. Pine S84°W 70.47       | 4" J. Pine S40°W 17.0             |
| Cedar Post SE 92                | *G.D.H. witness               |                                   |
|                                 | Cedar Post East 37            |                                   |

SIGNED BY Kenneth J. Ostling DATE 5-15-79  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CRAWFORD COUNTY