

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 ^{N.} R. 3 ^{W.}	L-1
2. PROPERTY CONTROLLING IN SECTION 1 _____	T. 25 ^{N.} R. 3 ^{W.}	8; 12; 13
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} R. _____ ^{E.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 8, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. - Description of original monument and accessories and/or subsequent restoration~~
C. (continued)


13
Set 5/8" Rod w/RLS Cap &
cedar post
10" J. Pine S63°E 42.0
6" J. Pine S09°W 27.44

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
L-1 Corner in place from previous survey, origin unknown, but used in subsequent surveys.

- 8 Set by standard survey procedure for the subdivision of sections, to identify State land boundary.
- 12 Set corner by standard survey procedure for the subdivision of sections.
- 13 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1	8	12
Found RR Rail	Set 5/8" Rod w/RLS Cap & cedar post	Set 5/8" Rod w/RLS Cap & cedar post
6" J. Pine S38°W 27.62	5" J. Pine N73°E 10.98	4" R. Pine N32°W 19.7
P.K. in P.P. S41°E 22.84	5" J. Pine N45°W 9.6	3" R. Pine S55°W 33.27
5" J. Pine S33°E 22.95		
Cedar Post South 19		



SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY