

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR. 3 W.

Crawford COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 13, 14, 23, 24

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER 9" Red Oak - N 28 E - 31 Links

7" W. Oak - S 25 E - 61 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. One probable original B.T. still in place, badly burned.

Corner was placed and witnessed April 13, 1954.

SURVEYORS SEAL

SIGNED *Alan C. Ash* DATE 10/22/54
REGISTERED LAND SURVEYOR