

2

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR 3 W

Crawford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 14 and 15

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" J. Pine	-	S60E	-	42 links

10" J. Pine	-	S6W	-	72 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division Land Surveyor while completing a partial resurvey of this township. Set corner by peopotionate measurement between section corners, - midpoint, on line- . Government B¹s all gone. Falls very near an old fence corner with faint fence rolls east and south. Good corners north and south.

Corner was placed and witnessed Aug 20, 1959.

SURVEYORS SEAL

SIGNED Kenneth J. O'Leary DATE 8/28/59
REGISTERED LAND SURVEYOR