

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

CRAWFORD COUNTY

Supercedes same described corner record
dated 7/25/69


T 25 N R 3 W

DESCRIPTION OF CORNER 1/4 corner common to Secs. 11-12

CORNER MONUMENT Set DNR Monument below surface of road

DATE MONUMENT PLACED AND WITNESSED 5-17-72

WITNESSES TO CORNER..... 4" J. Pine S 58 W 61.8



3" J. Pine N 45 W 79.2

6" J. Pine S 45 E 165.2

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Recovered position for corner as established in 1959 survey and subdivision of Sec. 12 by R. T. Ostling, R.L.S. Corner was set midpoint on line between section corners, as confirmed by our 1970 survey of Sec. 11. A 1" iron bar, noted as a "wild corner", is about 5.5' South and 3.6' East of true position, origin unknown, but generally in the same relative position as another invalid pipe at the section corner 1/2 mile North. Believe this position best conforms to the surveys and occupation of surrounding sections.

SURVEYOR'S SEAL

SIGNED *Ronald Ostling* DATE 5-17-72
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68