

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*Completed*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 <sup>N.</sup> ●, R. 3 <sup>W.</sup> ●	G-9; H-11
2. PROPERTY CONTROLLING IN SECTION 27	T. 25 <sup>N.</sup> ●, R. 3 <sup>W.</sup> ●	12; 13
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> ●, R. _____ <sup>W.</sup> ●	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on September 24, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**


**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- G-9 Found ½ iron bar, as established in previous survey by Ostling Surveys, Inc.
- H-11 Found 1" pipe as restored by G. D. Henning from U.S.B.T. in 1948.
- 12 Set by standard survey procedure for the subdivision of sections.
- 13 Set by standard survey procedure for the subdivision of sections.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-9	H-11	12
Set DNR Monument	Left 1" pipe in place	Set 2½' of 1" pipe & red top post
8" J. Pine N34W 75.1'	8" J. Pine S45W 22.7'	7" J. Pine N85E 18.2'
8" Maple N73E 41.4' (in clump)	16" R. Pine N44W 62.8'	6" Spruce N32W 8.5'
	13	
	Set 2½' of 1" pipe & red top post	
	9" Balsam N43E 17.4'	
	7" Balsam N30W 18.5'	

SIGNED BY *Kenneth J. Ostling* DATE 11/23/73  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)