

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 N. R. 3 ●	G-10; H-10
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. 25 N. R. 3 ●	G-10/3; 3; 8
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 24, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original and/or subsequent restoration~~
 C. (continued)

3	8
Set 2½' of 1" pipe	Set 2½' of 1" pipe & red top post
15" W. Oak S65E 61.45'	4" W. Oak N30W 11.1'
11" Bl. Oak S43E 67.5'	8" Bl. Oak N73E 27.3'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- G-10 Found spike set in Ostling Surveys, Inc. survey, also referenced by MDSH survey.
- H-10 Set corner at calculated intersection of true ¼ lines, as per standard survey procedure.
- G-10/3 Set property corner as required by standard survey procedure for subdivision of section.
- 3 Set by standard survey procedure for the subdivision of sections.
- 8 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10	H-10	G-10/3
Set DNR Mon. red top post 30' west	Set 2½' of 1" pipe & red top post	Set 2½' of 1" pipe
13" Bl. Oak N85E 75.1'	13" Cedar N80E 16.1'	19" Bl. Oak N67E 83.5'
Tw. 11" Bl. Oaks S43E 72.0'	12" Cedar S53E 46.9'	8" Poplar N37E 80.2'
		Set 1'x½" rerod East 33.0'

SIGNED BY Kenneth J. Ostling
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 12/30/73



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____