

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Crawford</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>25N</u> R <u>3W</u>	<u>L-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>25N</u> R <u>3W</u>	<u>15</u>
	S <u>24</u> T <u>25N</u> R <u>3W</u>	<u>11</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl R. Johnson, in a field survey on May 30, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 L-8 - Set at true computed intersection of $\frac{1}{4}$ lines.
 15 - Set midway and on line between $\frac{1}{4}$ corner and section corner.
 11 - Set by standard procedure for subdividing a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-8 - <u>Center of Sec. 24</u> Set D.N.R. Monument 6" J. Pine N27°W 24.4' 6" J. Pine S31°E 20.3' 1" Pipe N42°E 52.0' 8" J. Pine S81°W 18.3' Cedar Post Due West 10'	15 - <u>W1/8, South side of Section 24</u> Set 5/8" bar w/cap 8" Spruce N51°E 45.5' 6" J. Pine S67°E 19.8'	11 - <u>Center, SW$\frac{1}{4}$ Sec. 24</u> Set 5/8" bar w/cap 12" J. Pine S36°W 50.0' 4" J. Pine S85°E 26.4'
---	---	---

Signed by Carl Johnson
 Surveyor's Michigan License No. 30083

