

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
CRAMFORD  
 (County)

	Located In:	Corner Code =#
1. Public Land Survey	T <u>25M</u> R <u>3W</u>	<u>A-10, A-11,</u>
	T _____ R _____	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>31</u> T _____ R _____	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on JULY 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10	A-11	B-11	1
FD REROD FOR N 1/4 COR S-30. COR WAS FD & ACCEPTED BY P.S. F.J.ARLETH IN 1989 SURVEY. FD IRON IN CONC N82°E, 5.55' IS PROBABLY M.SCHAAF (CONS DEPT FORESTER/SURVEYOR IN 1920-40s) CORNER, NOT ACCEPTED THIS SURVEY. CTR OF N-S GRAVEL RD IS EAST 27' & TRAIL ROAD TO WEST IS NORTH 13'. CTR OF PIPE LINE SIGN #32 IS S54°W, 23.25'.	FD REROD FOR SW COR SEC 30. FITS OTHER CORNERS FD IN SECTION 30 TO N & E.	FD IRON ROD FOR S 1/4 COR SECTION 30. COR FITS MARK DONE BY P.S. F.J.ARLETH IN NW 1/4 OF S-30 IN 1989. FM COR IS 2' SOUTH AND 2' WEST. FENCE RUNS NORTH & WEST.	ACCEPTED FD 1/2" REROD FOR NE COR OF FRL NW 1/4 OF FRL NW 1/4, SECTION 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10	A-11	B-11	1
FD 1/2" REROD, BENT. REPLACED WITH 5/8" X 32" REROD. SET CED POST EAST 1.5'	FD. 1/2" REROD. IN CTR OAK RD & TRAIL WEST.	FD 1/2" IR ROD. SET CED POST. (UPPER BLAZES & SIDE NAILS)	FD 1/2" REROD. SET CARSONITE POST.
8" J PINE N71°E 92.54'	POWER POLE N50°W 34.97'	20" RED PINE N25°W 7.57'	14" JACK PINE S52°W 10.95'
POWER POLE S85°E 58.06'	14" W PINE S73°W 44.56'	12" JACK PINE S73°W 28.33'	6" J PINE N18°W 11.35'
4" J PINE N18°W 44.17'	6" J PINE S54°W 51.44'	10" JACK PINE S12°E 33.75'	8" J PINE S52°E 5.94'
10" J PINE S20°W 43.01'	18" J PINE N49°E 47.79'	8" JACK PINE N62°E 27.66'	3" TW J PINE N50°E 15.24'
FD IRON IN CONC N82°E 5.55'			E-S FENCE COR POST (DOWN) S15°W 5.2'

Signed by Carl F. Roser

Date 6-29-95

Surveyor's Michigan License No. 12028

