

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Crawford</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>3W</u>	<u>B-5</u>
	T <u>25N</u> R <u>3W</u>	<u>C-6</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on May 28, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-5 G.L.O. Addison Brewer 1852 set quarter section post
 Wit: Pine 18 N63°W 49 links
 Pine 8 S05°W 14 links

C-6 G.L.O. Addison Brewer 1852 set quarter section post
 Wit: Pine 8 N76°E 24 links
 Pine 12 N78°W 25 links

Liber 119, Page 185, July 1972 C. Eugene Ostling R.L.S.
 #12026 found 1/2" bar for corner.
 Wit: J. Pine N75°E 82.27'
 J. Pine S80°E 80.34'
 J. Pine S52°E 90.40'

Liber 120, Page 167, May 1971 C. Eugene Ostling R.L.S.
 #12026 shows a found iron for the corner. No witnesses given.

July 19, 1976 George Henning R.L.S. #2240 found a 1/2" bar for the corner. No witnesses given

Liber 312, Page 298, April 1990 Marvin E. Myers P.S.
 # 31600 shows corner on the Certificate of Survey. No witnesses given.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-5 Found 1/2" rod fitting C. Eugene Ostling's and George Henning's survey in section 18. Placed a 1" X 32" pipe with standard DNR monument over top.

C-6 Found a 1/2" rod center line of Grayling road fitting C. Eugene Ostling's and Marvin E. Myer's survey in section 18 added P.S. cap #33981.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 1" X 32" pipe with standard DNR monument
 Wit: 5" J. Pine N44°E 18.96'
 4" R. Pine N82°E 3.29'
 6" Oak S09°W 22.17'
 4" J. Pine S72°W 7.01'
 Centerline of Southbound U.S. 27 West 115'±
 Carsonite Post North 1'±

C-6 Found 1/2" rod in a monument box
 Wit: 12" Oak S67°W 42.58'
 10" J. Pine N41°W 76.38'
 10" J. Pine N66°E 47.58'
 9" R. Pine N69°E 38.14'
 Carsonite Post West 33'±

Signed by: _____

Carl T. Kiiskila

Date: _____

7-1-03

Surveyor's Michigan License No.: 33981

