

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Crawford (County)	Located In	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>3W</u>	<u>D4</u>
	T _____ R _____	_____
2. Property Controlling in Section	S <u>8</u> T <u>25N</u> R <u>3W</u>	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on January 19, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			●		8		9		10		11	
5				●									
6	15			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-4 This corner position was not established during the original government survey.

George D. Henning RLS #2240 Sept. 1980 subdivision plat "Skyline Forest Estates" L.253 P.20 found 1/2" rod no witnesses on plat.

5- George D. Henning RLS #2240 Sept. 1980 subdivision plat "Skyline Forest Estates" L.253 P.20 set 1/2" rod no witnesses on plat.

Consumers Power Company survey drawing H.A.Rhines 1992 found 1/2" rered inline fence East Wit: 10" Oak S51°W 16.62' S.E. side nail, 10" Oak S26°E 15.28' N.E. side nail, 10" Oak due West 8.46' S. side nail, 16" Oak N31°E 6.98' S.E. side nail

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

D-4 Found 1/2" rod fitting G.D. Henning's distances North and East well.

5- Found 1/2" capped rod H.L.S. #2240 fitting G.D. Henning's distances North and South well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-4 Found 1/2" rod
 Wit: *10" Oak S54°W 16.64'
 *10" Oak N88°W 8.74'
 *16" Oak N25°E 6.92'
 *10" Oak S20°E 15.28'

5- Found 1/2" capped rod H.L.S. #2240
 Wit: Utility pole N81°E 29.95'
 5" Oak S70°W 14.38'
 2" Cherry S15°W 21.36'
 4" Cherry N07°E 42.18'
 Posts and Wire East and South

*Old witnesses by others

Signed by:

Carl T Kiiskila

Date:

11-27-01

Surveyor's Michigan License No.:

33981

