

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD  
(County)

Located In:

Corner Code #

- |                                       |                          |             |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey                 | T <u>25N</u> R <u>4W</u> | <u>A-10</u> |
|                                       | T _____ R _____          | _____       |
|                                       | T _____ R _____          | _____       |
|                                       | T _____ R _____          | _____       |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

17 AUG 99 12:33 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**LIBER 4 PAGE 28**

I, Marvin E. Myers, in a field survey on 10-16, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		18		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO - 1839 J.H. Mullett, DS                      1930's M. Schaaf  
MON - POST    Mon - Iron (Sunk)  
Wit: 18" Y. PINE N64°W 25 LKS.  
18" S. PINE S58°W 36 LKS.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1 1/2"x18" Iron pipe with concrete base (typical Schaaf), 2' deep in centerline of North-South trail. Accepted Pipe as the best available evidence of the Original Corner. Placed Standard Crawford County.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon - Std. Crawford County Monument  
Wit: Spike in SE side 3" J. Pine N24°E 30.94  
Spike in N. side 4" J. Pine S57°W 70.95  
Spike in NW side 6" R. Pine S15°W 126.70  
North face of Petroleum pipeline warning sign (metal fence post) S31°W 91.14



CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE June 7, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date June 9, 1999