

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located in:

Corner Code #

- 1. Public Land Survey Sec. 31 T 26 NR 4W
 Sec. 6 T 25 NR 4W
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

B-13
B-1

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
19 DEC 97 2:38 P.M.
SANDRA MOORE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat LIBER 3
5. Private Claims _____

PAGE 291

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, Marvin E. Myers, in a field survey on September, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O.
April 16, 1839
H. Brevoort D.S. &
James H. Mullet D.S.
Mon: Post
Wit: 10" Pine N37 1/2°E 30 links
12" Pine N09°W 11 links

Michigan Department of Conservation
Billy D. Buckler R.L.S. July 31, 1957
This corner established by proportionate measurement.
Mon: 1" pipe with 4" brass cap
Wit: 8" Black Oak N14°W 18 links
7" Black Oak S85°E 67 links

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Oct 14, 1997
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" pipe with remnants of a Conservation Department cap.
Found Oak stump N45°W 11.93'
Found Oak Stump S85°E 44.45'
Accepted 1" pipe as a reestablishment of the position of the Original Government corner.
Replaced pipe with Standard Crawford County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Standard Crawford County Monument
Set Nail & tag in N. side 4" Poplar 134° 16.54'
Set Nail & tag in West side 3" Oak 215° 15.66'
Set Nail & tag in South side 2" Poplar 313° 23.14'
Set Nail & tag in West side 3" Oak 347° 11.39'
Set Nail & tag in South side 4" Maple in clump 314° 72.15'

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date _____

