

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |                          |               |
|---------------------------------------|--------------------------|---------------|
| <u>Crawford</u><br>(County)           | Located In:              | Corner Code # |
| 1. Public Land Survey                 | T <u>25N</u> R <u>4W</u> | <u>B-9</u>    |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**LIBER 4 PAGE 34**

I, Marvin E. Myers, in a field survey on August 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O - 1852, Addison Brewer. D.S.      1930's M. Schaaf  
Mon. - Post                                      Mon - Iron  
8" S. Pine N31°W 215 lks.  
8" S. Pine S54°E 138 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1/2"x18" iron bar in side a 2"x13" pipe encased in concrete (typical Schaaf) 2.5' South of the centerline of Fletcher Road in line with trail roads North and South. Accepted 1/2"x18" bar as the best available evidence of the position of the Original Corner. Replaced 1/2" bar with Standard Crawford County Monument in pavement monument box.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon: Standard Crawford County Monument in pavement monument box.  
Wit: Spike in West face 3" Jack Pine S10°E 64.29'  
Spike in East face 6" Jack Pine N19°E 114.49'  
Spike in East face 8" Jack Pine N7°W 138.02'  
Spike in NE face 8" Jack Pine N48°W 112.92'

**CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE June 7 1999**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
County Surveyor**



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date June 9, 1999

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED  
17 AUG 99 12:35 P.M.  
SANDRA NOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |