

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

For corners in

Crawford

(County)

Located In:

Corner Code #

1. Public Land Survey

T 25N R 4W

B-11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**LIBER 4 PAGE 26**

I, Marvin E. Myers, in a field survey on August 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O - 1852, Addison Brewer. D.S.      1930's M. Schaaf  
Mon. - Post                                      Mon - Iron  
28" W. Pine N20°W 44 lks.  
18" W. Pine S36°E 14 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 2"x12" pipe with concrete base in intersection of trail roads North, South, East & West (typical Schaaf monument). Accepted pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon: Standard County Monument.  
Wit: Spike in 12" Red Oak N44°E 15.57'  
Spike in 10" Red Oak N47°W 19.26'  
Spike in 8" Red Oak S42°W 56.28'  
Spike in 12" Red Oak S12°E 32.46'  
Carsonite Post N30°W 21.15

17 AUG 99 12:33 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11	●												
12	31		32		33		34		35		36		
13													



CRAWFORD COUNTY  
PEER GROUP APPROVAL

DATE June 7, 1999

Marvin E. Myers M.E.S.  
Marvin E. Myers, P.S.  
County Surveyor

Signed by

Marvin E. Myers

Date June 9, 1999

Surveyor's Michigan License No. 31600