

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD

(County)

Located In:

Corner Code #

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_  
T 25N R 4W

B-13

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LIBER 4 PAGE 06

I, Marvin E. Myers, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, D.S.

Mon - Post

Wit: 10" W. Oak N56°E 46 lks.

11" Yellow Pine N48°W 35 lks.

Marcus Schaaf 1940's

Mon - Iron Set

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Schaaf 1 1/2" pipe in concrete. Accepted pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Monument.

Wit: West edge of Carsonite Post N52°E 19.50

Nail & tag SE side 4" Maple N61°E 20.27

Nail & tag SW side 5" W. Pine S28°E 48.65

Nail & tag SW side 4" Maple (clump) N46°W 20.36

CRAWFORD COUNTY

PEER GROUP APPROVAL

DATE June 7, 1999

*Marvin E. Myers*

Marvin E. Myers, P.S.  
County Surveyor



Signed by

*Marvin E. Myers*

Surveyor's Michigan License No. 31600

Date

June 8, 1999

Register of Deeds Stamp & File Number

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

17 AUG 99 12:29 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													