

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

For corners in

<u>Crawford</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>4W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

17 AUG 99 12:33 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 4 PAGE 22

I, Marvin E. Myers, in a field survey on Dec 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|---|---|---|--|
| C-7 | G.L.O - 1852 Addison P. Brewer, DS
Mon. - Set S. Pine Post
12" S. Pine N56°W 46 lks.
10" S. Pine S32°E 47 lks. | May 1879 Co. Surveyor's Book
Mon - not given
Wit: 12" S. Pine S08 ½°E 277 lks.
12" S. Pine N20 ½°E 276 lks. | June 27, 1923 E. S. Houghton, #1122
Mon - Set Clay Tile Monument

1930's M. Schaaf
Mon: Iron |
| L. 2, P. 192 LCRC Sept 1978 K. Ostling #10068 | Mon - Fd 2" Pipe in concrete in road intersection,
old Schaaf mon., replaced with DNR mon. | L234, P509 April 1985 M. MacDonald #22438
Mon - Found DNR Mon.
Wit: 12" Pine Stump N26°E 108.6
DNR nail & Tag in U. Pole NW 51.3 | |
| Wit: 6" J. Pine N26°E 108.64
Nail in P. Pole N51°W 51.32
Cedar Post South 40.00 | | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Standard DNR monument; found nail & tag in UP N51°W 51.3; found Cedar Post S04°W 39.35; found nail in NE side 6" J. Pine S45°E 56.84 Accepted DNR monument as the best available evidence of the position of the Original Corner. Left DNR monument in place

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Standard DNR Monument.

- Wit: Nail & tag in UP N51°W 51.3
Cedar Post S04°W 39.35
Nail in NE side 6" J. Pine S45°E 56.84
E. Edge of Stop Sign Post S35°W 33.2
Carsonite Post N34°W 38.2

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE June 7, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 34600



Date June 9, 1999