

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

For corners in

Crawford

(County)

Located In:

Corner Code #

17 AUG 99 12:33 P.M.

- 1. Public Land Survey T 25N R 4W C-B
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LIBER 4 PAGE 24

I, Marvin E. Myers, in a field survey on Dec 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1852 A. P. Brewer, DS 1930's M. Schaaf
Mon. - Set Post Mon - Iron
Wit: 8" S. Pine N49°W 47 lks.
6" S. Pine N73°E 9 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x18" bar in center of 2"x12" Iron Pipe with 5"x8"x12" concrete base (typical Schaaf) in the North track of W. Godfroy Road. Accepted as the best available evidence of the position of the Original Corner. Replaced 1/2" bar and pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument.
Wit: Carsonite post North 33.00
Spike S. side 10" J. Pine N34°W 49.29
Spike NW side 9" J. Pine N39°E 41.83
Spike W. side 13" Norway Due South 41.33
East edge of Pipeline warning sign post S54°W 18.25
Centerline of N-S Road West 54'±

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE June 7, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date June 9, 1999