

MAR 29 2000

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>4W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

17 AUG 99 12:30 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**LIBER 4 PAGE 11**

I, Marvin E. Myers, in a field survey on August 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O - 1852, A. P. Brewer. D.S. Mon. - Post Wit: 7" S. Pine N19°W 38 lks. 8" S. Pine S17°E 17 lks.	Norman F. Parker, R.L.S.#16939 Survey L.192, P.499 dated 1980 Mon: DNR pipe Wit: none provided	Norman F. Parker, R.L.S.#16939 Survey L.192, P.500 dated 1980 Mon: DNR pipe (1 1/4" pipe) Wit: none provided
--	---	---

1930's M. Schaaf  
Mon - Iron

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1 1/4"x18" pipe with concrete base (typical Schaaf Monument) in intersection of trail roads North, South, East, and West. Found (dead) blazed 24" J. Pine S23°E 18.4 Accepted pipe as the best available evidence of the position of the Original Corner. Replaced 1 1/2" Pipe with Standard Crawford County Monument.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon - Standard County Monument.  
Wit: Spike in SW side 12" J. Pine S13°E 31.39  
Spike in SE side 6" J. Pine S35°W 53.02  
Spike in S. side 4" J. Pine N63°W 49.75  
Spike in NW side 4" Poplar N52°E 43.44  
Carsonite Post S54°W 55.17

**CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE June 7, 1999**

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date June 9, 1999