

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford  
(County)

Located In:

Corner Code #

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_  
T 25N R 4W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

C-13

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LIBER 4 PAGE 07

I, Marvin E. Myers, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, D.S.                      Marcus Schaaf 1940's  
Mon - Post    Mon - Iron Set  
Wit: 17" Yellow Pine N45°E 25 lks.  
      10" Yellow Pine N33°W 80 lks.  
GLO - August 1852 Addison P. Brewer, D.S.  
Mon - Post  
Wit: 8" Dead S. Pine S19°E 14 lks.  
      12" Dead S. Pine S35°W 53 lks.

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED  
17 AUG 99 12:30 P.M.  
SANDRA MOORE  
REGISTER OF DEEDS  
  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found Schaaf 1 1/2" pipe in concrete. Accepted pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Mon: Standard Crawford County Monument.  
Wit: West edge of Carsonite Post N71°E 31.0  
Nail & tag NW side 5" W. Oak N78°E 33.40  
Nail & tag SW side 2" Cherry S48°E 30.74  
Nail & tag W. side 7" R. Oak N15°W 38.96

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE June 7, 1999  
*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31800

Date June 9, 1999