

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

For corners in

Crawford Located In: Corner Code #  
(County)

1. Public Land Survey T 25N R 4W D-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

17 AUG 99 12:32 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**LIBER 4 PAGE 20**

I, Marvin E. Myers, in a field survey on Dec 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1852 Addison P. Brewer, DS  
Mon. - Set W. Oak Post  
Wit: 16" Y. Pine N58°E 7 lks.  
14" Y. Pine S36°W 42 lks.

L2, P. 192 LCRC Sept 1978  
K. J. Ostling #10068  
Mon- Fd. 2" Pipe 3' South of Centerline  
E-W Road Replaced with DNR Mon.  
Wit: Nail & tag 14" W. Oak S63°W 59.8  
Nail & tag 8" J. Pine S08°E 56.25  
Cedar Post Southeast 40.00

L. 234, P. 509 April 1985  
M. MacDonald # 22438  
Mon - Fd. DNR Mon.  
Wit: Fence Corner SW 46.6  
Face U. Pole NW 44.7  
DNR Cedar Post SE 39.5 to nail & tag

May 1879 Co. Surveyor's Book  
Mon - not given  
Wit: 16" Y. Pine S56 1/2°W 52 lks

1930's M. Schaaf  
Mon - Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Standard DNR; found DNR Cedar Post S26°E 39.5 (recorded as 40); found face of UP N28°W 44.3 (recorded as 44.7); found fence corner post S52°W 46.0 (recorded as 46.6); found nail in E. side 21" W. Oak S63°W 59.2 (recorded as 59.8)  
Accepted DNR monument as the best available evidence of the position of the Original Corner. Left DNR Monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard DNR Monument.  
Wit: DNR Cedar Post S26°E 39.5  
Face of UP N28°W 44.3  
Face of Fence corner post S52°W 46.0  
Nail in E. side 21" W. Oak S63°W 59.2  
Carsonite Post N54°E 54'±

CRAWFORD COUNTY  
PEER GROUP APPROVAL

DATE June 7, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date June 9, 1999