

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

17 AUG 99 12:33 P.M.

SANDRA MOORE
REGISTER OF DEEDS

For corners in

Crawford

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>25N</u> R <u>4W</u>	<u>D-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims **LIBER 4 PAGE 23**

I, Marvin E. Myers, in a field survey on Dec 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1930's M. Schaaf
Mon - Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4"x12" Pipe with 6"x8"x12" concrete base (typical Schaaf); found nail S. side 6" J. Pine S70°W 41.1; found nail N. side Norway S43°E 63.75; D-7 is N01°08'51"E 2627.41; D-9 is S01°07'00"W 2639.72; C-8 is S89°47'56"W 2635.21; E-8 is N89°47'40"E 2634.50 Accepted pipe as a careful and faithful establishment of the position of the Corner. Replaced Pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument.

Wit: Nail S. side 6" J. Pine S70°W 41.1
Nail N. side Norway S43°E 63.75
Nail W. side 8" J. Pine S23°W 56.6
Nail NW side 4" Maple N41°E 40.84
Carsonite Post N40°W 40.70

CRAWFORD COUNTY

PEER GROUP APPROVAL

DATE June 7, 1999

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by

Marvin E. Myers

Date June 9, 1999

Surveyor's Michigan License No. 31600