

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

17 AUG 99 12:35 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>4W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 4 PAGE 33

I, Marvin E. Myers, in a field survey on Dec 29, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1852 Addison P. Brewer, DS Mon. - Set Post 8" S. Pine N06°E 34 lks. 9" S. Pine S03°W 23 lks.	1930's M. Schaaf Mon - Iron	L. 234, P. 509 April 1985 M. MacDonald #22438 Mon - Found PK nail with tag Wit: 14" Pine SW 37.6 12" TW. Pine SE 60.9
---	--------------------------------	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Pk nail with tag in asphalt and accessories recorded in L. 234, P. 509. Found 2" pipe in concrete base (typical Schaaf) 2 feet below asphalt. Accepted pipe as the best available evidence of the Position of the Original Corner. Replaced PK nail with Standard Crawford County Monument in pavement monument box over top of 2" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Set Standard Crawford County Monument in pavement monument box.
Wit: Steel post S45°E 49.3
Found spike in 12" J. Pine N17°W 62.9
6"x6" Guard Post N40°E 41.28
Found spike SE side 13" R. Pine S43°W 95.08

**CRAWFORD COUNTY
PEER GROUP APPROVAL**
DATE June 7, 1999
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date June 9, 1999