

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	
	T	25N	R 4W
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

D-13

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 4 PAGE 08

I, Marvin E. Myers, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, D.S.	Marcus Schaaf 1940's
Mon - Post	Mon - Iron Set
Wit: 7" Pitch Pine N64°E 26 lks.	
7" Pitch Pine N46°W 34 lks.	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Schaaf 1 1/2" pipe in concrete. Accepted pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Monument.
Wit: West edge of Carsonite Post N51°E 33.78
Nail in E. side 3" J. Pine S30°E 69.21
Nail in NE side 3" J. Pine N54°W 41.59
Nail in NW side 5" J. Pine N37°E 44.48

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
17 AUG 99 12:30 P.M.
SANDRA MOORE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number



CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE June 7, 1999
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date June 9, 1999