

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

Crawford
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 26N R 4W
T 25N R 4W
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

E-13
E-1

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
19 DEC 97 2:38 P.M.
SANDRA MOORE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

LIBER 3 PAGE 294

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		1	
5												
6	18		17		16		15		14		1	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		21	
11												
12	31		32		33		34		35		31	
13												

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. Michigan Department of Conservation
 April 16, 1839 Billy D. Buckler R.L.S. Dec. 21, 1956
 H. Brevoort D.S. & James H. Mullet D.S. Corner set from probable NW original BT stump. Good corner north and east and probable line tree stump south.
 Mon: Post Mon: 1" pipe with 4" bras cap below surface of road
 Wit: 20" Yellow Pine N27°W 51 links Wit: 8" Black Oak N42°E 22 1/2 links
 12" White Oak N56°E 22 links 7" Black Oak N41°W 70 links

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE OCT 16, 1997
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Corner removed by Military traffic; reestablished by proportional measure, checks well with Conservation Dept Survey 1956 direction and distance. Accepted position as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Mon - Standard Crawford County Monument.
 Set nail & tag in E. side 3" White Oak N24°E 30.86'
 Set nail & tag in SE side 6" Black Oak N77°E 37.26'
 Set nail & tag in S. side 8" Black Oak S71°E 95.68'
 Set nail & tag in W. side 6" Maple in clump S20°E



Signed by *Marvin E. Myers*
 Surveyor's Michigan License No. 31600

Date OCT 23, 1997