

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

17 AUG 99 12:33 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

For corners in

Crawford
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 25N R 4W E-8
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LIBER 4 PAGE 25

I, Marvin E. Myers, in a field survey on Dec 29, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1852 Addison P. Brewer, DS
Mon. - Set Post
9" S. Pine S37°W 69 lks.
8" S. Pine S18°E 46 lks.
5" S. Pine S00°34'W 150 lks.

May 1879 Co. Surveyor Book
Mon - not given
Wit: 6" S. Pine S64 1/2°E 93 lks.
7" S. Pine N38 1/2°E 70 lks.

1930's M. Schaaf
Mon - Iron (sunk)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" x18" Iron Pipe 0.5 deep with concrete base (typical Schaaf). Three foot East of Centerline of trail road North & 18 feet East of trail road South & 5 feet South of E-W trail road centerline. Accepted pipe as the best available evidence of the position of the Original Government Corner. Replaced pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Set Standard Crawford County Monument.
Wit: Carsonite Post N28°E 42.15
Spike in W. side 3" Poplar S08°E 16.60
Spike S. side 3" Oak N36°W 62.93
Spike SE side 13" B. Oak S89°W 63.05
Spike W. side 3" Poplar N45°E 42.91

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE June 7, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date June 9, 1999