

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

CRAWFORD  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 25N R 4W      E-10
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.          S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

17 AUG 99 12:31 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

LIBER 4 PAGE 12

I, Marvin E. Myers, in a field survey on 10-16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 A. P. Brewer, DS                    1930's M. Schaaf  
 MON - POST                                      Mon - Iron (Sunk)  
 Wit:    8" S. PINE N82°E 15 LKS.  
        7" S. PINE S56°W 33 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" Iron pipe with concrete base (typical Schaaf), 2' deep in centerline of old East-West trail. Accepted 2" Pipe as the best available evidence of the Original Corner. Placed Standard Crawford County Monument over top of 2" pipe left in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Std. Crawford County Monument  
 Wit: Spike in 6" W. Pine S32°W 13.25  
        Spike in 8" W. Pine S48°E 24.00  
        Spike in 10" R. Pine N63°W 4.36  
        Spike in 6" J. Pine S52°W 15.05  
        Carsonite Post S06°E 11.9

CRAWFORD COUNTY  
 PEER GROUP APPROVAL  
 DATE June 7, 1999

*Marvin E. Myers*  
 Marvin E. Myers, P.S.  
 County Surveyor



Signed by *Marvin E. Myers*  
 Surveyor's Michigan License No. 31600

Date June 9, 1999