

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>25N</u> R <u>4W</u> | <u>E-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 4 PAGE 13

I, Marvin E. Myers, in a field survey on 10-16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 A. P. Brewer, DS 1930's± M. Schaaf
MON - POST Mon - Iron
Wit: 12" Y. PINE N35°W 5 LKS.
10" Y. PINE S80°E 55 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" Iron Pipe with concrete base (typical Schaaf) in Centerline of East-West trail and trail to the South. Accepted 2" pipe as the best available evidence of the position of the Original Corner. Raised by placing Standard Crawford County Monument on top of 2" Pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument.
Wit: Carsonite Post N07°E 7.9
Nail & tag S. side 2" twin Maple N13°W 18.84
Nail & tag N. side 8" Poplar S64°W 16.71
Nail & tag W. side 10" Maple S17°E 25.99
Nail & tag N. side 10" J. Pine S61°E 25.30

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

17 AUG 99 12:31 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE June 7, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date June 9, 1999