

MAR 29 2000

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 CRAWFORD COUNTY  
 RECORDED

For corners in

CRAWFORD  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

E-13

17 AUG 99 12:30 P.M.

SANDRA MOORE  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims LIBER 4 PAGE 09

I, Marvin E. Myers, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O - 1839 John Brink, D.S.  
 Mon - Post  
 Wit: 8" Pitch Pine N80°E 16 lks.  
 7" Pitch Pine N61°W 26 lks.

Marcus Schaaf 1940's  
 Mon - Iron Set

GLO - August 1852 Addison P. Brewer, D.S.  
 Mon - Post  
 Wit: 8" S. Pine S25°E 10 lks.  
 8" S. Pine S35°W 15 lks.

L1, P ? LCRC K. Ostling, RLS Dec 1979  
 Mon - Found Schaaf 1 1/2" Pipe Set DNR Monument  
 Wit: 12" R. Pine S25°E 59.84  
 14" R. Pine S70°E 68.76  
 Cedar Post South 15.00

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found DNR Monument 0.3 below surface in fire lane N-S, & E-W; found DNR post South; found blazed 22" R. Pine S25°E 59.84; found blazed 11" J. Pine N65°E 69.06; found blazed 22" R. Pine S70°E 68.76  
 Accepted DNR Monument as the best available evidence of the position of the Original Corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon: DNR monument left in place  
 Wit: Nail & Tag in 22" Norway S22°E 60.26  
 Nail & Tag in 11" J. Pine N65°E 69.06  
 Nail & Tag in 6" J. Pine N53°W 60.70  
 Carsonite Post N46°E 38.48

**CRAWFORD COUNTY**  
**PEER GROUP APPROVAL**  
 DATE June 7, 1999

*Marvin E. Myers*  
 Marvin E. Myers, P.S.  
 County Surveyor



Signed by Marvin E. Myers  
 Surveyor's Michigan License No. 31600

Date June 9, 1999