

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD

(County)

Located In:

Corner Code #

STATE OF MICHIGAN
 CRAWFORD COUNTY
 RECORDED

17 AUG 99 12:34 P.M.

SANDRA MOORE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | | |
|---------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>25N</u> R <u>4W</u> | F-9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER 4 PAGE 30

I, Marvin E. Myers, in a field survey on 10-16, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 A. P. Brewer, DS 1930's± M. Schaaf
 MON - POST Mon - Iron
 Wit: 8" DEAD S. PINE N74°W 36 LKS.
 8" S. PINE S42°30'E 327 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x12" Pipe in concrete base (typical Schaaf) over cabin or wagon pin (very old and decayed) 1' below pipe in Centerline of East-West road (Fletcher Road). Check distance West to E-9 2630.84; distance East to G-9 2631.00
 Accepted as the best available evidence of the position of the Original Corner. Replaced 1" pipe and pin with Standard Crawford County Monument in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument in pavement monument box.
 Wit: Carsonite Post S35°E 46.07
 Spike in NE side 18" J. Pine N38°W 71.93
 Spike in W. side 12" J. Pine S32°E 81.27
 Spike in W. side 18" W. Pine S17°E 90.59
 Spike in W. side 18" J. Pine S45°W 99.86

CRAWFORD COUNTY
 PEER GROUP APPROVAL
 DATE June 7, 1999

Marvin E. Myers
 Marvin E. Myers, P.S.
 County Surveyor



Signed by *Marvin E. Myers*
 Surveyor's Michigan License No. 31600

Date June 9, 1999