

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---|-----|------|
| 1. Public Land Survey | T | R | |
| | T | 25N | R 4W |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

F-13

4. Lot No. _____, Recorded Plat _____

5. Private Claims LIBER 4 PAGE 10

I, Marvin E. Myers, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, D.S.
Mon - Post
Wit: 10" Pitch Pine N70°E 52 lks.
7" Pitch Pine N61°W 26 lks.

Marcus Schaaf 1940's
Mon - Iron Set

L1, P ? LCRC K. Ostling, RLS Dec 1979
Mon - Found Schaaf 2" Pipe left in place
Wit: 8" R. Pine N51°E 190.00
7" W. Oak N71°W 158.26
Cedar Post South 30.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" pipe Schaaf Monument 1.0 below surface in fire lane N-S, & E-W; found DNR post South lying flat; found 15" W. Oak N71°W 158.26 Accepted 2" pipe as the best available evidence of the position of the Original Corner. Replaced pipe with standard Crawford County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Monument.
Wit: 15" W. Oak N71°W 158.26
Nail & tag in W. side 8" J. Pine N12°W 37.85
Nail & tag 4" R. Pine N43°E 41.52
Nail & tag 4" J. Pine S41°W 39.30

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

17 AUG 99 12:30 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE June 7, 1999

Marvin E. Myers M.E.S.

Marvin E. Myers, P.S.
County Surveyor

Date June 8, 1999

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

