

**SURVEY & REMONUMENTATION**

APR 07 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 26NR 4W T 25N R 4W T ___ R ___ T ___ R ___	G-13 G-1
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED  
19 DEC 97 2:39 P.M.  
SANDRA MOORE  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ **LIBER**  
5. Private Claims \_\_\_\_\_

3 PAGE 296

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Marvin E. Myers, in a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O. Michigan Department of Conservation  
April 16, 1839 Billy D. Buckler; October 25, 1956  
H. Brevoort D.S. & Corner established from original BT's  
James H. Mullet D.S. Mon: 1" pipe with 4" brass cap  
Mon: Post Wit: 8" Red Oak S34°W 54 1/2 links  
Wit: 24" Pine N15°W 38 links 7" Red Oak N80°E 35 links  
20" Yellow Pine N34°E 93 links

**CRAWFORD COUNTY**  
**PEER GROUP APPROVAL**  
DATE OCT 15, 1997

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1" pipe and portions of brass cap in clear cut. Replace in exact location with a Standard Crawford County Monument.  
Found Red Oak stump S34°W 36'  
Accepted as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Mon - Standard Crawford County Monument.  
Set nail and tag in North face 8" Maple N59°W 84.10'  
Set nail and tag in North face 8" Poplar N89°W 78.52'  
Set nail and tag in North side 10" Black Oak S67°W 78.51'  
Set nail and tag in East face 5" Beach in clump S37°E 55.52'  
Set Carsonite Post North 1'

Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600

Date OCT 23

