

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

For corners in

CRAWFORD  
(County)

Located In:

Corner Code #

17 AUG 99 12:34 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>25N</u> R <u>4W</u> | <u>G-9</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

LIBER 4 PAGE 29

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on 10-15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 A. P. Brewer, DS	1930's± M. Schaaf	NORMAN F. PARKER, OCTOBER 30, 1973
MON - POST	Mon - Iron	(LIBER 1, PAGE 180)
Wit: 12" Y. PINE N05°E 45 LKS.		MON - 1/2" IRON IN CENTERLINE, 26' EAST OF TRAIL
14" Y. PINE S81°W 90 LKS.		Wit: 7' J. PINE S25°E 50.42'
		10" J. PINE S40°W 80.50'
		2" IRON PIPE N30°E 47.12'
		10" J. PINE N50°W 72.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x18" Iron bar over 2"x15" Iron Pipe with concrete base (typical Schaaf) in Centerline of East-West road (Fletcher Road), and 25'±. East of North-South trail. Accepted as the best available evidence of the position of the Original Government Corner. Replaced with Standard Crawford Monument in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument in pavement monument box.  
Wit: Found Spike in E. side 5" J. Pine S14°W 66.96  
Found Spike W. side 6" J. Pine N2°W 41.89  
2" pipe (new pipeline marker post) N30°E 43.86  
Spike in SE side 4" J. Pine N64°E 62.93  
Carsonite Post N15°E 27.43

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE June 7, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*

Date June 9, 1999

Surveyor's Michigan License No. 31600