

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD

(County)

Located In:

Corner Code #

1. Public Land Survey

T 25N R 4W

G-10

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER 4 PAGE 16

I, Marvin E. Myers, in a field survey on 10-16, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1852 A.P. Brewer, DS 1930's± M. Schaaf
MON - POST Mon - Iron
Wit: 8" TAMARACK N50°E 24 LKS.
6" TAMARACK N22°W 23 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" Iron Pipe sticking 3' out of ground, and 1.5' in ground. Accepted as the best available evidence of the position of the Original Corner. Left Pipe in place (in wet swamp) place 1/2"x18" bar and cap along West side for identification purposes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MON - 2" Pipe with 1/2" x18" bar and cap along West side for identification purposes.
Wit: NAIL in 6" W. PINE S32°W 13.25'
NAIL in 8" W. PINE S48°E 24.00'
NAIL in 10" R. PINE N63°W 4.36'
NAIL in 6" J. PINE S52°W 15.05'

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

17 AUG 99 12:31 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE June 7, 1999

Marvin E. Myers M.E.S.

Marvin E. Myers, P.S.
County Surveyor



Signed by Marvin E. Myers

Date June 9, 1999

Surveyor's Michigan License No. 31600