

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N R 4W G-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

**LIBER 4 PAGE 15**

I, Marvin E. Myers, in a field survey on 10-16, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO -- 1852 A. P. Brewer, DS 1930's M. Schaaf  
MON -- POST Mon - Iron  
Wit: 10" Y. PINE N45°E 43 LKS.  
10" Y. PINE S42°W 38 LKS.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 2"x18" Iron Pipe with concrete base (typical Schaaf) 1.5' deep in Centerline of East-West trail, 5' east of Centerline of trail to the South, and 35' east of Centerline of trail to the North. Accepted 2" Iron Pipe as the best available evidence of the position of the Original corner. Replaced Pipe with Standard Crawford County Monument.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

MON -- Standard Crawford County Monument.  
Wit: NAIL 14" OAK N13°E 12.24'  
NAIL 10" OAK S72°E 16.00'  
NAIL 16" OAK S61°W 51.60'  
NAIL 12" MAPLE N44°W 20.00'  
Carsonite Post Due North 10.85

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

17 AUG 99 12:31 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE June 7, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date June 9, 1999