

SURVEY & REMONUMENTATION

APR 07 1998

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 26NR 4W I-13
 T 25N R 4W I-1
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER 3 PAGE 298

STATE OF MICHIGAN
 CRAWFORD COUNTY
 RECORDED

19 DEC 97 2:39 P.M.

SANDRA MOORE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4			3		2
3												1
4	7			8			9			10		11
5												12
6	18			17			16			15		14
7												13
8	19			20			21			22		23
9												24
10	30			29			28			27		26
11												25
12	31			32			33			34		35
13												36

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. April 16, 1839 H. Brevoort D.S. & James H. Mullet D.S. Mon: Post Wit: 12' Beech N60W 19 links 10' Beech N11E 42 links	Norman F. Parker R.L.S. #16939 April 25, 1979 Liber 177 Page 322 Mon: 1 1/4" pipe Wit: Power Pole N45E 47.7' Power Pole N86W 31.6' Telephone Pole S36W 55.9'
--	---

**CRAWFORD COUNTY
 PEER GROUP APPROVAL
 DATE OCT 16, 1997**

Marvin E. Myers
**Marvin E. Myers, P.S.
 County Surveyor**

Norman F. Parker R.L.S. #16939 April 25, 1979 Liber 177 Page 95 Mon: 1 1/4" pipe Wit: No witnesses provided	Norman F. Parker R.L.S. #16939 April 25, 1979 LCRC Liber 2 Page 261 Mon.: Found 1 1/4" pipe used in previous surveys Wit: Power Pole N45E 47.7' Power pole N86W 31.6 Telephone Pole S36W 55.9"
Norman F. Parker R.L.S. #16939 Sept. 28, 1979 Liber 193 Page 144 Mon: 1 1/4" pipe Wit: No Witnesses provided	Norman F. Parker R.L.S. #16939 Jan. 12, 1981 Liber 194 Page 377 Mon: 1 1/4" pipe in road intersection Wit: No witnesses provided
Norman F. Parker R.L.S. #16939 Sept. 17, 1980 Liber 237 Page 482 Mon: 1 1/4" pipe Wit: No Witnesses provided	Norman F. Parker R.L.S. #16939 Dec. 2, 1989 Liber 305 Page 422 No Monument description or witnesses provided



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1 1/4" Pipe, replaced with Standard Crawford County Monument
 Found Power Pole N45E 47.7'
 Found New Power Pole N86W 31.6'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Mon- Standard Crawford County Monument
 Wit: Nail & Tag in SE face U. Pole Az. 287° 48.26
 Nail & Tag in SW face 10" Maple Az. 60° 80.41
 Nail & Tag in W face 6" W. Birch Az. 143° 103.35
 Nail & Tag in N. Face U. Pole Az. 221° 32.83

Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

Date OCT 23, 1997