

SURVEY & REMONUMENTATION

APR 07 1998

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|------------------------------------|-------------------------|---------------|
| <u>Crawford</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>26NR 4W</u> | <u>J-13</u> |
| | T <u>25N R 4W</u> | <u>J-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

[Signature]

STATE OF MICHIGAN
 CRAWFORD COUNTY
 RECORDED

19 DEC 97 2:39 P.M.

SANDRA MOORE
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 299

I, Marvin E. Myers, in a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| G.L.O. April 16, 1839 H. Brevoort D.S. & James H. Mullet D.S. Mon: Post Wit: 10" Beech N62°W 22 links 12" Beech N60°E 7 links | Norman F. Parker R.L.S.#16939 L2 P261, 25 April 1979 Mon: Found R.R. spike Wit: 6" Maple S06°E 39.8' 18" Twin Maple S46°W 59.9' |
| Norman F. Parker R.L.S.#16939 L177 P95, 25 April 1979 Mon: Found R.R. spike Wit: 6" Maple S06°E 39.8' 18" Twin Maple S46°W 59.9' Fence Corner N17°E 30.15' | Norman F. Parker R.L.S.#16939 L177 P322, 25 April 1979 Mon: Found R.R. spike Wit: 6" Maple S06°E 39.8' 18" Twin Maple S46°W 59.9' |
| Norman F. Parker R.L.S.#16939 L177 P322, 25 April 1979 Mon: Found R.R. spike Wit: 6" Maple S06°E 39.8' 18" Twin Maple S46°W 59.9' | Norman F. Parker R.L.S.#16939 L181 P608, 28 September 1979 Mon: Found R.R. spike Wit: 6" Maple S06°E 39.8' 18" Twin Maple S46°W 59.9' |
| Norman F. Parker R.L.S.#16939 L191 P09, 27 August 1980 L191 P315, 27 August 1980 Wit: 6" Maple S06°E 39.8' 18" Twin Maple S46°W 59.9' | |

**CRAWFORD COUNTY
 PEER GROUP APPROVAL
 DATE OCT 16, 1997**

[Signature]
**Marvin E. Myers, P.S.
 County Surveyor**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Rail Road Spike. Replaced with Standard Crawford County Monument in pavement box. Found Fence Corner N17°E 30.55'; Found 6" Maple S06°E 39.85'; Found 18" Twin Maple S46°W 59.9'; Found Utility Pole N61°E 46.05 Accepted position as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Mon - Standard Crawford County Monument in pavement monument box.
 Wit: Set nail in E. side Fence Corner N22°E 30.18
 Set nail in SE side Utility Pole N63°E 46.51
 Set nail in E. side 8" Maple S03°E 40.24
 Set nail in NE side 38" Maple S50°W 60.29
 Set Carsonite Post North 28±

Signed by *[Signature]*
 Surveyor's Michigan License No. 31600

