

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	√ T 26NR 4W / √ T 25N R 4W / T _____ R _____ T _____ R _____	K-13 <u>K-1</u>
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

19 DEC 97 2:39 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

3 PAGE 300

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	15		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35			
13												

I, Marvin E. Myers, In a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. April 16, 1839 Robert T. Ostling R.L.S. # Survey of Section 1, T25N, R4W
 - H. Brevoort D.S. & James H. Mullet D.S. Mon: Post Dec 1960
Wit: 12" Hemlock N63E 56 links Mon: Iron beneath pavement
18" Beech N46 1/2E 28 links Wit: None provided
 - Norman F. Parker R.L.S. #16939 LCRCLiber 2, Page 260 Dec 1960
Aug 10, 1981 Mon: 1/2" over iron pipe in blacktop
Wit: 12" Maple N52E 53.6' Wit: 12" Maple N52E 53.6'
8" Jack Pine S46W 95.6' 10" Jack Pine S46W 95.6'
 - Norman F. Parker R.L.S. #16939 L191P09 Aug. 27, 1980 Dec 1960
Mon: 1/2" Iron "G.D. Henning" Mon: Iron beneath pavement
Wit: 12" Maple N52E 53.6' Wit: 12" Maple N52E 53.6'
10" Jack Pine S46W 95.6' 10" Jack Pine S46W 95.6'
 - Norman F. Parker R.L.S. #16939 L206P115 Aug. 10, 1981 Dec 1960
Mon: 1/2" Iron "G.D. Henning" Mon: 1/2" Iron "G.D. Henning"
Wit: 12" Maple N52E 53.6' Wit: 12" Maple N52E 53.6'
10" Jack Pine S46W 95.6' 10" Jack Pine S46W 95.6'
 - Norman F. Parker R.L.S. #16939 L217 P 624 June 22, 1983 Dec 1960
Mon: 1/2" Iron Mon: 1/2" Iron over larger iron
Wit: No witnesses provided Wit: No witnesses provided

**CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE OCT 16, 1997**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron; overtop of 1/2" Iron 2.3 feet deep (left this Iron in place). Found dead 12" maple with blaze at base N52 53.6'; Found 16" Jack Pine with blaze and "G. D. Henning" tag S46°W 95.6'. Accepted 1/2" Iron as the best available evidence of the position of the Original Corner.
Replaced with Standard Crawford County Monument in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate location and position of the corner:

Mon - Standard Crawford County Monument in pavement monument box.
Wit: Set nail & tag in NW side Utility Pole Az. 233° 42.70
Set nail & tag in SW side Fence Corner Post Az. 145° 46.65
Set nail & tag in SE side 14" Red Pine Az. 63° 80.18
Found nail & tag 16" Jack Pine S46°W 95.60

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date OCT 16 1997

