

**SURVEY & REMONUMENTATION**

APR 07 1998

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

Crawford  
 (County)

Located In:

Corner Code #

- |                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | T <u>26NR 4W</u>        | <u>L-13</u> |
|                                    | T <u>25N R 4W</u>       | <u>L-1</u>  |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

STATE OF MICHIGAN  
 CRAWFORD COUNTY  
 RECORDED

19 DEC 97 2:40 P.H.

SANDRA MOORE  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**LIBER**

**3 PAGE 301**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |  |
|--|--|
| G.L.O.<br>April 16, 1839<br>H. Brevoort D.S. &<br>James H. Mullet D.S.<br>Mon: Post<br>Wit: 10" Beech N62°W 22 links<br>12" Beech N60°E 07 links   | Robert T. Ostling<br>Dec. 1960<br>No description provided                                  |
| Norman F. Parker R.L.S. #16939<br>1983 Liber 217 Page 108<br>Mon: 1/2" iron bar cap #16939<br>Wit: Old Blaze 24" Oak N24°W 57.6'<br>Old Blaze 12" Maple N17°E 45.5'<br>Old Blaze 18" Poplar S19°W 51.6'                                  | Norman F. Parker R.L.S. #16939<br>1983 Liber 217 Page 624<br>Mon: 1/2" iron bar cap #16939 |
| Marvin E. Myers P.S. #31600 June 11, 1990<br>Mon: Found 1/2" bar and cap of record<br>Wit: Nail in SE face 6" poplar S45°W 57.2<br>Nail in NE face 22" R. Oak N24°W 58.6<br>Nail in NW face 9" Maple N16°E 45.6<br>20" Poplar N16°E 52.3 |  |

Note: Ostling Dec 1960 work map indicates:  
 1/2x18" bar & cap set midway & on line  
 Wit: 15" Oak N28°20'W 57.9  
 8" Maple N12°50'E 45.5  
 14" Poplar S14°50'W 51.8

**CRAWFORD COUNTY  
 PEER GROUP APPROVAL  
 DATE OCT 16, 1997**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
 County Surveyor**

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1/2" iron bar cap #16939, replace 1/2"x6" bar & cap with Standard Crawford County Monument.  
 Found Old Blaze with spike 24" Oak N24°W 57.6'  
 Found Old Blaze with spike 12" Maple N17°E 45.5'  
 Found Old Blaze with spike 18" Poplar S19°W 51.6'  
 Accepted position as the best available evidence of the position of the Original Corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon - Standard Crawford County Monument in pavement monument box.  
 Wit: Set nail & tag NW side 10" Oak Az 248° 64.81  
 Set nail & tag SW side 6" Maple Az 138° 51.16  
 Found nail in NW side 9" Maple N16°E 45.6  
 Carsonite Post North 27±

Signed by *Marvin E. Myers*  
 Surveyor's Michigan License No. 31600

Date 10-23, 1997

